

Technology Development

Overview and Outlook



Kirk McDonald, for Alan Bross

MAP Collaboration Meeting
JLAB. March 4. 2011

Outline



- R&D Goals
- Status to date
 - FY 11 Milestones & *beyond*
- Outlook

Technology Development

What it is



- Normal Conducting RF (in cooling sections)
 - MuCool program - MuCool Test Area
- Superconducting RF (in accelerators)
- Magnets
- Targets and Absorbers

Primary Goals



- Establish the viability of the concepts and components that will be used in the design reports
 - Neutrino Factory Reference Design Report (NF-RDR)
 - Muon Collider Design Feasibility Study Report (MC-DFSR)
- Establish the engineering performance parameters to be assumed in the design studies
- Provide a good basis for cost estimates.

Tech Dev Milestones



- FY11
 - Complete engineering design for Be-wall rf cavity
 - Complete engineering design for new 805 MHz pillbox
 - Complete initial high power rf (HPRF) cavity beam test
 - Initial analysis of target magnet specifications
 - Fabricate and test small 400 Hz dipole model
- FY12
 - Fabricate and begin testing Be-wall rf cavity
 - Fabricate and test new 805 MHz pillbox
 - Prepare rf test cavity with atomic layer deposition (ALD) coating
 - Begin fabrication of 1.5 m 400 Hz dipole model
 - Detailed analysis of target magnet specifications
 - Complete conceptual design of IR quadrupole
- FY13
 - Test 201-MHz cavity with coupling coil in MTA
 - Detail design of HCC solenoid
 - Complete test of 400 Hz dipole model
 - Test ALD cavity
- FY14
 - Detailed design of target solenoid
 - HTS demo coil test with quench protection
- FY15
 - Fabricate components for 6D cooling bench test
- FY16
 - Complete components for 6D cooling bench test
 - Assemble components for 6D cooling bench test
 - Complete detailed design of > 30-T solenoid

RF Program

Primary Goal: *RF Down Selecting*



- Down selection of cooling RF cavities will be based on the outcome of our experimental studies.
 - The cavities must work at an acceptable RF gradient (requirements are, of course, dependent on the position along the channel, *i.e.*, phase rotation, bunching, initial cooling, final cooling, *etc.*) in a multi-Tesla magnetic field.
 - Engineering, fabrication, integration and cost of the cavity and RF power must also be considered
 - 2 Years out if we are lucky

Phase I RF Program

Status



- Complete first round of tests on Magnetic Insulation
 - Done
 - Second round with identical cavity, but with orientation $E \parallel B$
- Beam tests of high pressure H_2 filled cavity
 - Beam line commissioning underway
 - First Test this month
- Retest refurbished 805 pillbox
 - Done. Unfortunately, the results were very poor. Investigating!
- Materials tests: Be
 - Button cavity test
 - Waiting on post-mortem of pillbox test
 - Be-wall cavity
 - All-seasons cavity
 - Complete new design
- Atomic Layer Deposition (ALD)
 - Button test with 805 pillbox
 - Special-purpose ALD cavity
- 201 MHz tests
 - Retest 201 with repaired couplers

RF Reports at This Meeting



- A. DeMello: 10+1 cavities for MICE under fabrication (not Tech Dev).
- D. Li: 201 and 805 MHz cavities for test; Be windows look good.
- J. Norem: RF breakdown at nanoscale mitigated by coating.
- Y. Torun: MTA operational!
- A. Tollestrup: Model of arcing in high pressure RF cavity.
- K. Yonehara: Beam test soon of high pressure RF cavity.
- A. Moretti: Box cavity test: 8% reduction in usable MV/m per deg between 3-T B field and surface.
- M. Jana: Box cavity + button test: > 50% reduction in usable MV/m when 3-T is perpendicular to surface.

Outlook:

RF Testing Queue



- Primary goal is to collect a lot more data with as many test vehicles as possible. Next 12-18 months:
 - 805 pillbox (modified & refurbished?)
 - Investigating
 - New series of materials & processing (Cu) tests with Buttons (*pending*)
 - Initial test of high power (HP) button cavity with proton beam
 - 201 MHz cavity coupler repair and re-test
 - 2nd HPRF beam test as needed
 - Rectangular box cavity with $B \parallel E$
 - 2nd rectangular box cavity with $B \perp E$
 - New pillbox is near ready (Muon's Inc.)
 - Can operate under pressure or vacuum
 - Has capability to replace end-walls (Be)
 - *Complete design of Be-wall cavity (maybe test in this time frame)*
 - ALD cavity
 - Special-purpose cavity for processing in-situ with Atomic Layer Deposition
 - Test MICE production 201 MHz cavity in realistic B field [> 18 months out]

Magnet R&D - Overview



- Neutrino Factory and Muon Collider accelerator complexes require magnets with quite challenging parameters
 - Target Capture Solenoid
 - What is the most effective scheme to protect the target solenoid from the radiation environment near to the target?
 - HTS solenoid R&D to assess the parameters that are likely to be achieved
 - What is the highest practical achievable solenoid field & what is the R&D required before these solenoids can be built?
 - HCC magnet R&D to assess the feasibility of this type of cooling channel and
 - Eventually build a demonstration magnet for a HCC test section (dependent on success of HP RF tests)
 - Magnet design R&D for collider ring and IR magnets that have to deal with the expected high level of energy deposition from μ decay electrons
 - What is the optimal design for the collider ring magnets that will enable them to operate in the presence of the decay electrons? Paper studies only (with D&S group)
 - Fast Ramping Magnets utilized in rapid-cycling synchrotron for final acceleration for the MC



Magnet Reports at This Meeting

- S. Virostek: MICE solenoid repair (not Tech Dev).
- K. Lee: Lithium lens simulations.
- R. Weggel: Conceptual design of 20-T target solenoid, and of open midplane dipoles for decay ring.
- R. Gupta: Vision of 20-T HTS solenoid.
- J. Tompkins: Two 4-coil segments of helical solenoid tested; YBCO coil tested in 14-T field.
- T. Shen: Round HTS conductor now to 600 A/mm² at 20 T and 4K.

Outlook: Magnets



- Next 12-18 months
 - HTS
 - 1st Small coil multi-element test reaches 10T
 - HCC
 - Test of 2nd R&D HCC 4-coil magnet
 - Conceptual design for HCC solenoids which meets specs
 - Accelerator
 - Conceptual designs for arc dipoles and quadrupoles
 - Conceptual design for IR quadrupole
 - RCS
 - Small prototype 400Hz dipole – fabricate and test
 - 1.5m dipole prototype – begin fabrication
 - Target Capture
 - Detailed analysis of insert and outsert solenoids; thermal, mechanical, and magnetic requirements (*maybe a bit further out than 18 months*)

Targetry



- All targetry activity now under Technology Development.
 - Design
 - Target solenoid array (Weggel)
 - Magnet and shielding layout (Graves)
 - Simulation
 - Magnetohydrodynamics of mercury jet (Samulyak)
 - Mercury flow through nozzle (Ladiende, Yan)
 - Particle production and energy deposition (Back, Ding, Souchlas (+ Hansen, Prior))
 - Engineering
 - Hardware Development

Targetry Reports at This Meeting



- R. Weggel: Conceptual design of 20-T target solenoid.
- N. Souchlas: Energy Deposition in the target system.
- R. Gupta: Vision of 20-T HTS solenoid.

Outlook: Targetry



- Revised baseline recently established
 - 20-T solenoid inner radius 120 cm, \Rightarrow 3 GJ
- Emphasis on design and simulation for \geq 6 months
 - Review choice of 20-T
 - Revise solenoid array accordingly
 - Initiate conceptual design of shield (+coolant flow).
 - Continue modeling of mercury jet: pipe flow, free jet flow, beam interaction.
- Engineering, costing for IDS RDR still several months away
 - Mercury flow loop, including collection pool
 - Beam windows
 - Tungsten carbide shield (+ water cooling)
 - 6-T room temperature copper magnet (+ services)
 - Superconducting solenoid array (+ cryo plant for \approx 1 kW at 4K)
 - Remote handling system, hot cells
 - Civil construction
- Hardware tests of mercury jet and/or WC+water only if indicated by above

Summary



- The MAP effort in TD focuses on cooling
 - You All Know Why
- The RF program continues to take a multi-pronged attack
 - The MTA is now a smoothly running facility
 - Multi-frequency RF
 - SC magnet(s) & cryogenics infrastructure
 - Extensive RF diagnostic instrumentation
 - Clean room for RF cavity work
 - H₂ handling infrastructure
 - p beam line
 - However, this complexity (test area is now a “primary beam enclosure”), has added significant overhead to our operations at present
 - We are working with the Fermilab safety groups to try to make operations more efficient

Summary II



- Magnet program also focuses primarily on cooling issues
 - Final cooling via very-high-field HTS solenoids
 - HCC solenoids as potential option
- But also addresses the other critical magnet issues for the MC complex
 - Ring magnets
 - Open-plane dipoles, quads, etc
 - Acceleration
 - Fast-ramping magnets

This Year



- Well, FY11 is turning out to be a real “pleasure”
- Even with the uncertainties, we think we can
 - Complete initial suite of experiments with HPRF
 - Buttons?
 - Retest 201 MHz prototype with new couplers
 - Test new cavities
 - All seasons
 - Box with E parallel to B (*maybe*)
 - Magnets
 - HCC/HTS/ (Check with John)
 - 400 Hz prototype (Check with Don)



END
